

SP00495 (Special Provisions for the 2024 Book)

(Bidding on or after: 09-01-26

Last updated: 06-08-26

~~Requires SP00735, SP00745, SP00756, SP00759, SP01030 & SP01040~~

~~Requires SP00641 when rock surfacing or aggregate base is required.~~

~~Requires, SP00705 when emulsified asphalt prime coat is required.~~

~~Requires SP00710 when emulsified asphalt surfacing is required.~~

~~Requires SP00730 when emulsified asphalt tack coat is required.~~

~~Requires SP00735 when EAC is required.~~

~~Requires SP00744 or SP00745 when ACP is required.~~

~~Requires SP00756 when concrete paving is required.~~

~~Requires SP00759 when sidewalk, curbs or driveways are required.~~

~~Requires SP01030 when seeding is required.~~

~~Requires SP01040 when topsoil or planting/landscaping is required.~~

)

SECTION 00495 - TRENCH RESURFACING

(Follow all instructions and make all edits with "Track Changes" turned on. If there are no instructions [purple text] above a subsection, paragraph, sentence, or bullet, then include it in the project. Delete all purple text before preparing the final document. All other modifications to this Section will require ODOT Technical Resource and State Specifications Engineer approval.)

Comply with Section 00495 of the Standard Specifications modified as follows:

00495.40(b) Emulsified Asphalt Concrete Paving - Replace this subsection, except for the subsection number and title, with the following:

When temporary Surfacing is required prior to placing permanent Surfacing, place EAC paving a minimum of 1 inch thick. Place temporary paving that is smooth with surface variations not greater than 1/2 inch from the Existing Surfacing. Ensure the joint between the temporary patch and existing surfaces is not greater than 1/4 inch high. Maintain the temporary Surfacing until the permanent Surfacing is placed. ACP mix may be used if approved.

00495.90 Payment - Replace the paragraph that begins "Payment will be payment ..." with the following paragraph:

Payment will be payment in full for furnishing and placing all Materials, and for providing all Equipment, labor, and Incidentals necessary to complete the Work as specified.